# Project Design Document: Greening of rural value chains for seeds cleaning and grading unit

# Project background

Arunodayagro Farmers Producer Company Limited is a 351-member farmer-producer organisation (FPO) incorporated in 2017. The details of FPO are mentioned below.

Table 1 Details of FPO

Name of FPO	Arunodayagro Farmers Producer Company Limited	
Address	At Takali Khandeshwari, Karjat District: Ahmednagar, Maharashtra,	
	India - 414402.	
Activity	Trading of agricultural produce	
Propose activity	Dal mill, chilly processing unit and cold storage	
Capacity of unit	3 TPH, 1 TPH, and 1800 MT respectively	
Produce	All grains, custard apple, guava, mango and all vegetables	
Number of operational days	300	
Connected load (kW)	228	

The raw material is sourced from the member and non-member farmers of FPO in the region. The value chain is as follows:



However, the processing unit will face challenges of high operation costs, a major component of which is electricity cost. This issue will result in low profitability of the unit.

## **Project description**

This project aims at the solarisation of unit by installing solar PV. The specifications of the proposed solar PV system and annual savings are as follows,

Table 2 Details of solar PV system

Solar photovoltaic panel system	456.75 kW
Annual mitigation of CO <sub>2</sub>	526.81-ton CO₂ per year
Average savings on annual electricity unit consumption	666849 units
Average saving on annual electricity bill	INR 8504368

<sup>\*</sup>Assumption:

<sup>1.</sup> Saving per unit electricity consumption INR 10 per KWh

<sup>2.</sup> Average power generation per KWp= 4 kWh/KWp/day

# Summary of investments

Total project cost is expected to be close to INR 251.21 lakhs that includes design, engineering, procurement, and installation. Per kW cost of solar PV is considered 50,000 Rs/kW with EE measures of INR 5000 per kW is considered.

**Sharing Technology** Capacit Qty Cost Value **Cost sharing** Relevan (Rs/unit (Nos (Rs.) scheme FPO Loan Govt subsid equity y 1 Project Cost\* 456.745 kW 1 2,28,37, 2,28,37, 45,67, 0 1,82,69 Solar 298 ,838 photovoltaic 96 298 460 panel system with battery 1 22.83.73 22,83,73 4,56,7 18,26,9 Energyefficient 0 46 84 measures Total 2,51,21, 2,51,21, 50,24, 0 2,00,96 20::0::8 028 ,822 206

Table 3 Capital Costs for the project

#### **Financial analysis**

A simple cash-flow analysis is below, with the conservative assumption that the equipment has a lifespan of 20 years.

### Project cost

The project cost of 251.21 lakh includes solar panel equipment cost and installation cost, other components of project cost are taken as zero as the plant is already proposed.

#### Means of finance

Regarding the implementation of solar rooftop installations for industrial consumers, no subsidies are accessible for this initiative. Consequently, the funding for the project will be undertaken by the FPO. The financial arrangement for this venture entails a 20% equity investment from the FPO and the remaining 80% through a loan arrangement. Additional specifics concerning the financing breakdown can be referenced in Table 4.

Table 4 Means of Financing

Means of Finance					
Total Financing required	INR lakhs	251.21			
Equity	%	20%			

<sup>\*</sup>Project cost includes all costs (plant and machinery, solar photovoltaic panel costs, et al), excluding land cost

<sup>\*\*</sup>Based on discussions held on the ground and their financial conditions, equity share ranges from 5% to 30%, hence has been assumed at 20%

Grant	%	0%
Debt	%	80%
Interest Rate (Per Annum)	%	12.00%
Moratorium	Years	1
Annual Instalment	Years	5
<b>Equity Component</b>	INR lakhs	50.24
<b>Grant Component</b>	INR lakhs	0
Debt Component	INR lakhs	200.97

Source: MP Ensystems Research

The financial indicators analysed by discounting cash flow at 10% and the summary is presented in **Table 5**.

Table 5 Estimated Financial Indicators

Financial Indicators	Estimated	Requirement
Net Present Worth	369.17	Should be positive
IRR	39%	> 10%
BCR	2.8	Should be >1.0
Payback period	5.2 years	

Source: MP Ensystems Research

The bank loan with interest is repayable within 5 years with a moratorium of one year.

The following specific attributes of ESG can further be achieved through the implementation of this project:

• There are a number of environmental opportunities including mitigation of carbon emissions, reduction of resource depletion. There are direct climate benefits to the project. The installation of roof-top solar results in the mitigation of 526.81 tonnes of CO<sub>2</sub> emissions every year.